## **GENERAL NOTES:**

Inverter / UPS: 8kW

Solar Charge Controller: 8kW

Wiring sized as per SANS10412-1 GFDI device built into UPS Solar array earthed with min 6mm copper All PV strings are fused

Note:

SLD:Conradie UPS and Solar Charger

C:\Users\kaloy\OneDrive\ ... Conradie SLD.dsn

29 May 2019

Date

Document

Sheets

1 of 1

Author K.Dimov Solar MD File

Revision

1.0

The SMD LynX Inverter is fitted with an internal interlocked physically separated change-over switch for off-grid SSEG certificate of compliance

